

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In: Corner Code #

1. Public Land Survey	T <u>42N</u> R <u>6W</u>	<u>61</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>10</u> T <u>42N</u> R <u>6W</u>	<u>15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 30 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (G1) Corner common to Sections 3-4 T42N-R06W and Sections 33-34 T43N-R06W. 1957 - Billy D. Buckler RLS re-monumented the corner in the original position from original bearing trees. Set 1" pipe with 4" brass cap. Witnesses: 8" Tamarack N45E 48 links, 9" W.Pine S55E 70 links, 6" Tamarack S21W 19 links.
 (15-Sec. 10) West 1/16 corner between Sections 10-15. Established in 1962 by Billy D. Buckler RLS midway and on line between Section and Quarter corners. Set 1" pipe with 4" aluminum cap. 16" W.Pine stump N12W 75.5 links. Corner lies 1 chain east of road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G1) Recovered the 1957 monument in good condition. The 1957 NBT Tamarack 6" SW is standing dead, with old blaze visible, at record bearing and distance. The 1957 W.Pine and Tamarack NE are now stumps. The original BTs noted in the 1957 record are gone.
 (15-Sec. 10) Recovered the 1962 monument in good condition. The 1962 witness stump is now gone. I found the monument to be 1.05' North and 1.27' East of the position of record and accept same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G1) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in: 10" twin Maple S43W 8.3' "S4 NBT" 5" Maple S16W 18.45' do 5" Balsam S36E 19.0' "S3 NBT" 6" Balsam N77E 20.5' "S34 NBT" Bearings are magnetic. Distances are to nail with tag.	(15) Found 1" ID I. pipe with 4" alum. MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in: 5" Cherry N78W 76.15' "W1/16 8T" 10" W. Birch S13W 87.4' do 8" Cherry S53E 39.6' do 10" Cherry N10W 48.0' do Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/15/04