

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>42N</u> R <u>6W</u>	<u>G3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 30 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3						●						
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. 1962 - Reestablished by Billy D. Buckler RLS using proportionate distance to corners east and west, and on line of blazes E-W. Set 1" pipe with 4" brass cap. 18" W.Pine S10E 70 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Recovered the 1962 monument in good condition and at record bearing and distance from a low-cut W.Pine stump, presumed to be the remains of the 1962 MNT. Distances to corners one mile north and south show that the Northing of this corner is only 19' south of the proportioned GLO position. The two miles from G5 to G1 measures 132' shorter than the GLO record. I accept the 1962 position as a careful and faithful reestablishment of the position of the original corner. The corner lies approx. 22' north of and E-W road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Found 1" ID 1. pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:
 8" Cherry N70W 29.9' "S4 MNT"
 5" W.Pine N23W 37.4' do
 6" Cherry S66W 70.7' "S9 MNT"
 12" W.Pine S75E 32.85' "S10 MNT"
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/15/04