

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S <u>10</u>	T <u>42N</u> R <u>6W</u>	<u>11</u>
	S <u>10</u>	T <u>42N</u> R <u>6W</u>	<u>8</u>
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 23 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2		1	
3												
4	7	8			9		10		11		12	
5												
6	18	17			16		15		14		13	
7												
8	19	20			21		22		23		24	
9												
10	30	29			28		27		26		25	
11												
12	31	32			33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (11-Sec. 10) Southwest 1/16 corner, Section 10. Not established in the original survey.
 (8-Sec. 10) West 1/16 corner, Section 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (11-Sec. 10) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (8-Sec. 10) Established the corner midway and on a straight line between Quarter corner 1317.51' west and Center of Section (unmonumented) 1317.51' east. The position for the corner falls on a large root. The monument was installed such that it is leaning to the west, the top center of the aluminum cap marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 8" W.Pine N63W 43.05' "SW1/16 NBT" 12" Cherry N48W 43.95' do twin 6" Cherry N61E 16.05' do 8" W.Pine S28W 41.25' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 18" Cedar S35W 3.45' "W1/16 BT" 18" Cedar S40E 8.1' do 24" Cedar S76E 13.4' do 18" Cedar N88E 17.95' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski Date 9/15/04
 Surveyor's Michigan License No. 33986