

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ S. _____ R. _____ E. _____ W. _____	15, Sec. 2 3, Sec. 2 10, Sec. 2
2. PROPERTY CONTROLLING IN SECTION <u>2</u> , T. <u>42</u> ,	N. _____ S. _____ R. <u>7</u> E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4/26 19 65, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
15, Sec. 2 Corner placed midway bet. Sec. Cor. to West and $\frac{1}{4}$ Cor. to East.

3, Sec. 2 Corner placed on a line and proportionate distance bet. $\frac{1}{4}$ Cor. to South and Closing Cor. to North.

10, Sec. 2 Corner placed on a line and midway bet. $\frac{1}{4}$ Cor. to North and Sec. Cor. to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

15, Sec. 2 Buried $1\frac{1}{4}$ " x 30" pipe in road.
Bearings:
5" Red Pine N33°W 76.2'
7" S. Maple S41°W 74.0'

3, Sec. 2 Buried $1\frac{1}{4}$ " x 30" iron pipe at corner.
Bearings:
8" Red Pine S88°W 50.0'
8" J. Pine S56°E 62.4'

10, Sec. 2 Buried $1\frac{1}{4}$ " x 30" pipe at corner
Bearings:

No Witnesses.

SIGNED BY Billy D. Buckler DATE 6/27/72

Billy D. Buckler
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____