

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
Mackinac Co. Two Corners

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. R. <u>7</u> E. W.	I-2 <u>16, Sec. 2</u>	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>2</u>	T. <u>42</u> N. R. <u>7</u> E. W.	_____	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	_____	
4. LOT NO. _____, RECORDED PLAT _____		_____	
5. PRIVATE CLAIMS _____		_____	

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4/27 1965, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

I-2 Original  $\frac{1}{4}$  Cor. bet. 2-3, set by H. Brevoort Jr., D.S. in 1845.  
Bearings were:

Beech 16" S68°E 12 Links  
Beech 9" S75°W 31 Links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

I-2 Found no evidence of original corner, so placed on line and a proportionate distance bet. Sec. Cor. to South and Closing Corner to South.

16, Sec. 2 Corner placed midway and on line bet.  $\frac{1}{4}$  Cor. to West and Sec. Cor. to East.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Buried 1 $\frac{1}{2}$ " x 30" iron pipe at both corners.

I-2 New Bearings:

7" Red Pine S60°W 45.3'  
9" Jack Pine S75°E 33.9'

16, Sec. 2 New Bearings:

9" Hard Maple S31°W 90.8'  
7" Hard Maple S34°E 66.3'

SIGNED BY Billy D. Buckler DATE 6/27/72  
Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_