

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N.R. 7 W.


Mackinac COUNTY

DESCRIPTION OF CORNER Closing Corner for Sections 2-3 on North boundary of Township.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 4/11/63.

WITNESSES TO CORNER..... 6" Red Pine (N.B.T.) S. 14° E., 93 Lks.



7" Red Pine (C.C. S. & N.B.T.) S. 7° W., 88 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established 17 links West of Section Corner 34-35, T. 43 N., R. 7 W. No evidence of original corner.

Note: This corner lies 17 Links West of Section Corner 34-35, T. 43N. R. 7 W.

Corner lies 67 Links North of Road to East and 1.53 Chs. East of North-South Road.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 8-5-63
REGISTERED LAND SURVEYOR