

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Mackinac Co. 3 Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>42</u> N. <u>8</u> E. R. <u>7</u> W.	<u>1-3</u> <u>1, Sec. 12</u> <u>2, Sec. 12</u>
2. PROPERTY CONTROLLING IN SECTION	<u>12</u> T. <u>42</u> N. <u>8</u> E. R. <u>7</u> W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4/26 1965, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 L-3 Original $\frac{1}{4}$ Cor. bet. Secs. 1-12, set by H. Breevort Jr., D.S. in 1845.
 Bearings were:
 Beech 10" N7 $\frac{1}{2}$ ⁰E 10 Links
 Beech 4" S44⁰W 15 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 L-3 Corner placed proportionate distance bet. Sec. Cor. to East and old Township road to West.
 1, Sec. 12 Corner placed on line and in line with old Township road to North.
 2, Sec. 12 Corner placed midway bet. Sec. Cor. to East and $\frac{1}{4}$ Cor. to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-3 Buried 1 $\frac{1}{4}$ " x 30" iron pipe at corner, (at all three corners)
 New Bearings:
 9" Beech S40⁰E 60.8'
 9" Hard Maple S47⁰W 50.3'
 1, Sec. 12 New Bearings:
 8" S. Maple S42⁰E 48.5'
 16" S. Maple N13⁰W 46.6'
 2, Sec. 12 New Bearings:
 15" H. Maple N32⁰W 65.6'
 9" S. Maple S22⁰W 54.6'

SIGNED BY Billy D. Buckler DATE 6/27/72
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)