

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Mackinac Co. Two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>42</u> N. <u>7</u> E. <u>W.</u>	<u>M-2</u> <u>14, Sec. 1</u>
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	T. <u>42</u> N. <u>7</u> E. <u>W.</u>	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 10/29 19 64, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-2 East $\frac{1}{4}$ Corner, Sec. 1, originally set by Austin Burt, D.S. in 1840.
Bearings were:
Fir 6" S41°W 11 Links
Hemlock 8" N79°W 18 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-2 Corner re-established midway and on line bet. two Sec. Cors. Found no evidence of original. Corner lies 6.0' West of trail road.

14, Sec. 1 This 1/16 Corner placed midway between Sec. Cor. to South and $\frac{1}{4}$ Cor. to North

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Placed 1" pipe with 4" aluminum cap at corner.
New Bearings:

12" W. Spruce N36°W 46.9'
12" W. Spruce N28°E 61.0'

14, Sec. 1 Buried 1" pipe with 4" aluminum cap at corner.
New Bearings:

14" Hard Maple S60°W 28.9'
8" Hard Maple N80°E 22.0'

SIGNED BY Billy D. Buckler DATE 6/27/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____