


MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION



# LAND CORNER RECORD

T. 42N N. R. 7W


Mackinac COUNTY

DESCRIPTION OF CORNER Meander corner bet. Secs. 7-8, on north shore of Lake Michigan

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 10-23-70

WITNESSES TO CORNER..... 9" Cedar (MC NBT) N11° 30.2'



9" Cedar (MC NBT) N81°W 17.9'

AND

CIRCLE CORNER REGISTERED

### DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This meander corner re-established in line with the mile to north end at record distance from the Sec. Cor. 4.50 chains to north. Found numerous cedars but none could be identified as original witnesses.

Corner lies in margin of timber edge, on lake shore.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 12-2-70