

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. <u>7</u> E. <u>W.</u>	<u>H-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>3</u>	T. <u>42</u> N. <u>7</u> E. <u>W.</u>	<u>12</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David Lobbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-12 & 11-30, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 2 Center Section 3. Not previously established.
- 2 South 1/16 Corner of Section 3. Not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 Set at the intersection of the N-S and E-W 1/4 lines of Section 3 by closed traverse.
- 2 Set mid point on line between the South 1/4 Corner and Center 1/4 Corner of Section 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

at D.N.P. Monument at both corners. Bearings are:

- |                              |                              |
|------------------------------|------------------------------|
| -2 12" R. Pine, S77°E, 22.3' | 12 10" W. Pine, S84°W, 37.1' |
| 7" R. Pine, N51°E, 14.2'     | 12" R. Maple, N12°W, 27.6'   |
| 7" h. Pine, N10°E, 33.2'     | 6" Beech, N25°E, 37.5'       |
| 8" W. Birch, N12°W, 11.0'    | 8" R. Maple, S32°E, 35.6'    |
|                              | 2" Pipe, N41°W, 37.6'        |

SIGNED BY

David B. Lobbitt  
David Lobbitt

DATE 12-21-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: