

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 7 E.	H-1
2. PROPERTY CONTROLLING IN SECTION 3	T. 42 N. R. 7 E.	5
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David Eabbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-12, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1 1/4 Corner on North side of Section 3. Corner was not set in original survey.
- North 1/16 Corner of Section 3. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1 Set corner midway on line between the NE and NW Section Corners of Section 3.
- Set corner by single proportionate measure between the North 1/4 corner and the center 1/4 corner of Section 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

at D.N.R. monument at both corners. Bearings are:

- | | |
|----------------------------|----------------------------|
| -1 6" J. Pine, S64°W, 6.3' | 5 8" J. Pine, N10°E, 15.4' |
| 7" J. Pine, N70°W, 32.3' | 6" R. Pine, S70°E, 24.6' |
| 12" R. Pine, N55°E, 11.85' | 7" J. Pine, S16°E, 19.9' |
| 10" R. Pine, S33°E, 23.6' | 12" R. Pine, S18°W, 19.95' |

SIGNED BY David B. Eabbitt DATE 12-21-81

David Eabbitt
SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: