

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION	1, T. 42 N. _____ S., R. 7 E. _____ W. _____	L-2, 8, 9
3. MISCELLANEOUS PROPERTY IN SECTION	_____, T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____	_____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-21, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-2 Center of Section 1. Not prev. established.
- 8 West 1/16 Corner of ^{E-W 1/4 line} Section 1. Not prev. established.
- 9 East 1/16 Corner of ^{E-W 1/4 line} Section 1. Not prev. established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-2 Set at intersection of E-W and N-S 1/4 lines of section 1.
- 8 Set M.P.O.L. between the center corner and the West 1/4 corner of section 1.
- 9 Set M.P.O.L. between the center corner and the East 1/4 corner of section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-2 8" Hemlock, S70°E, 16.5' & 8" H. Maple, S68°W, 17.85'. & 12" Hemlock, S84°W, 44.75' & 8" R. Maple, N15°E, 4.4'.
- 8 5" H. Maple, S21°E, 21.95' & 10" J. Pine, N81°W, 49.5' & 6" R. Pine, N60°W, 55.75'.
- 9 10" W. Pine, N82°E, 18.9' & 8" W. Pine, S29°W, 9.5' & 16" W. Pine, N10°W, 19.75'.

D.N.R. Monument was placed at all three corners.

SIGNED BY

David E. Babbitt

DATE 1-24-83

David E. Babbitt
SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____

DATE _____