

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MACKINAC CO.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>10</u> , T. <u>42</u>	N. S., R. <u>7</u> E. W.	<u>H-4, H-4&12, 5</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-23, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-4 Center of Section 10. Not prev. set.
- H-4&12 Property Corner on the North-South 1/4 Line of Section 10[635.19' South of the Center Corner; Not prev. set.
- 5 North 1/16 Corner of Section 10. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-4 Set at the intersection of a line westerly, from the east 1/4 corner, parallel to the north section line with a line southerly, from the north 1/4 corner, parallel to the east section line of section 10. Said parallel lines are the 1/4 lines of section 10 because south and west lines of section 10 fall in Lake Michigan.
- H-4&12 Set on the North-South 1/4 line of section 10, 635.19' south of the center of section, on the shore of Lake Michigan.
- 5 Set M.P.O.L. between the center of section and the north 1/4 corner of section 10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monuments set at all three corners.

H-4	6" W. Birch, S55°E, 41.3'	H-4&12	8" Cedar, N10°E, 20.4'	5	12" Cedar, N70°W, 154.75'
	10" W. Birch, S30°W, 6.4'		8" Cedar, N71°E, 38.9'		12" Cedar, S13°W, 77.15"
	8" W. Birch, N79°W, 29.7'		9" Cedar, S66°E, 36.0'		6" Balsam, N54°W, 136.04'
	6" R. Maple, N01°E, 39.8'		6" Cedar, S38°E, 12.5'		4" Spruce, S27°E, 29.65'

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 1-23-87

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: