

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MACKINAC CO.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 42 N. R. 7 E. W.	I-4 ✓
2. PROPERTY CONTROLLING IN SECTION 10	T. 42 N. R. 7 E. W.	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-17-, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-4 East 1/4 Corner of Section 10. OBT'S: 40.00 set 1/4 Section and Meander Post on Margin of Lake Michigan. Tam. 4", N04°W, 97 lks. & Tam. 4", N24°E, 82 lks.
- 7 North 1/16 Corner on East Side of Section 10. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-4 Set by extending the section line between sections 2 and 3 south to the shore of Lake Mich. and set 1/4 corner and meander corner monument at 2640' south of the corner common to sec's 2-3-10-11 as recorded in the G.L.O. notes. This position falls on the "Margin of Lake Mich." as recorded in the G.L.O. Notes. Also an Iron was found on this same line at 1021.77' south of the section corner common to sec's. 2-3-10-11.
- 7 Set M.P.O.L. between the N.E. Section Corner and the East 1/4 Corner of Section 10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monuments set at both corners.

- |                            |                            |
|----------------------------|----------------------------|
| I-4 6" Cedar, N15°W, 43.9' | 7 10" Cedar, N43°W, 10.30' |
| 7" Cedar, N03°E, 38.2'     | 12" Cedar, S39°W, 37.05'   |
| 8" Cedar, N32°E, 48.2'     | 14" Cedar, S40°E, 16.90'   |
| 6" Cedar, N79°E, 20.4'     | 12" Hemlock, N18°E, 36.30' |

SIGNED BY

*David B. Babbitt*

DATE 1-23-87

David B. Babbitt

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)