LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in		·	
	Nack inac (County)	Located in:	Corner Code ≠#
1.	Public Land Survey	T42NRJN_	L2
		T R	
		T R	
2.	Property Controlling	S1 T42N R7W_	
	in Section	S1 T42N RIW_	<u> </u>
3	Miscellaneous	STR	

Register of Deeds Stamp & File Number


4. Lot No. Recorded Plat

5. Private Claims

Property in Sec.

t, <u>\$tephan I, \$2752k0ski.</u>, in a field survey on <u>August. 17, 1993.</u>, 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

(L2) Center of Section 1. Corner established in 1982 and recorded by David B. Babbitt, RLS in 1983 at the intersection of E-W and N-S 1/4 lines. Babbitt placed a D.N.A. monument at the corner and the following witness trees: 8° Hemlock S70E 16.5', 8° H. Maple S88W 17.85', 12° Hemlock S84W 44.75', 8° R. Maple NFSE 4.4'.

(8-Sec. 1) West 1/16 corner of Section 1. Corner established in 1982 and recorded in 1983 by David 8. Babbitt, RLS at the M.P.O.L. between the Center 1/4 and the West 1/4 of Section 1. Babbitt placed a 1° pipe with a 4° aluminum MDNR tablet and the following witnesses: 5° H. Maple S21E 21.95', 10° J. Pine N81W 49.5', 6° R. Pine N60W 55.75'.

(9-Sec. 1) East 1/16 corner of Section 1. Corner established in 1982 and recorded in 1983 by David B. Babbitt, RLS as placed M.P.O.L. batween the center of section 1 and the east 1/4 corner. Monumented by 1° iron pipe and a 4° MDNR cap. Witnesses: 10° W. Pine N82E 18.9', 8° W. Pine S29W 9.5', 16° W. Pine N10W 19.75'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L2) Found the 1983 monument and accessories as described. Yerified the position of the monument with respect to the intersection of 1/4 lines as follows: determined the monument to be 1.04' north and 0.28' east of the intersection of 1/4 lines, the East and West 1/4 corners being reastablished in 1993. Accepted the monument as a careful and faithful determination of the corner. Marked new top blazes on the 1982 witness trees, placed measuring nails with tags, and remeasured, as described below.

(8-Sec. 1) Found Babbitt's monument at record bearing and from the 1982 accessories. Yerified the position of the monument as being 0.13' S. and 0.12' E. of midway and on a straight line between the Center of Section 1 and the West 1/4 Corner (reestablished in 1993). Accepted the monument as a careful and faithful determination of the corner. Marked a new top blaze on the 1983 witnesses, placed measuring nails with tags in same, and remeasured as described below.

(9-Sec. 1) Found Babbitt's monument at record bearing and distance from the 1982 witnesses. Verified the position of the monument as being 0.16' W. and 0.35' N. of midway and on a straight line between Center of Section and East 1/4 corner (reestablished in 1993). Accepted the monument as a careful and faithful determination of the corner. Marked new top blazes on the 1982 witness trees, placed measuring nails and tags in same, and remeasured as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(L2) Found 1" pipe with 4" MDMR cap.

12" Hemlock STOE 16.6"

10" H. Maple S68W 18.1"

14" Hemlock S84W 45.0"

12" R. Maple N15E 4.6"

an old 7" scribed hemlock post stands adjacent to the corner. Placed a location poster on a 6" maple at a trail approximately 132" east of the corner.

(8) Found 1° pipe with 4° MDNR cap.
7° H. Maple S21E 22.3° (1983 BT)
12° J. Pine M81W 49.5° (1983 BT)
8° R. Pine N60W 56.15° (1983 BT)
8lazed, scribed, and set a measuring nail with tag in:
10° Twin Maples M24E 25.3° "1/16S BT" an old 5° scribed balsam post stands adjacent to the monument.

(9) Found 1° pipe with 4° MONA cap.
14° W. Pine N82E 19.2° (1982 BT)
12° W. Pine S29W 9.6° (1982 BT)
20° W. Pine N10W 19.9° (1982 BT)
Blazed, scribed and set measuring nail with tag in:
8° Spruce S62E 21.0° 1/165 BT° an old 6° scribed W. Pine post stands adjacent to the monument.

Signed by Stephen J. Date SZYSZKOSKI Surveyor's Michigan License No. 3386 LAND SURVEYOR

10-14-43

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAM 26, 1971 Revised May 14, 1975 Revised Jan., 1983