

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Macquinnac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	_____	R	_____	_____			
	T	_____	R	_____	_____			
	T	_____	R	_____	_____			
	T	_____	R	_____	_____			
2. Property Controlling In Section	S	<u>12</u>	T	<u>42N</u>	R	<u>7W</u>	_____	<u>1</u>
	S	_____	T	_____	R	_____	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____	_____
	S	_____	T	_____	R	_____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on October 19, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 12) West 1/16 corner between Sections 1-12. Corner not established in the original survey. Corner previously established in 1965 by Billy O. Buckler, RLS: 1 1/4" x 30" iron pipe witnessed by 8" S. Maple S42E 48.5', 16" S. Maple N13W 46.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 12) Buckler's monument was not recovered. Remonumented the corner with a 1"x36" iron pipe capped with a plastic cap stamped "MICH DNR LS 33986". Placed the pipe on a straight line between monumented government corners 1320.89' east and west. Corner falls in center of E-W road. Found Buckler's two witness trees in place and at record bearing and distance from the remonumented corner. Placed measuring nails and tags in the 1965 BIs and remeasured as shown below. Marked two new bearing trees.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:



(1) Set 1" pipe with plastic cap 33986
 Blazed, scribed, and set measuring
 nails/tags in the following:
 5" Beech S55E 67.2' "N1/16 8T"
 5" Soft Maple N40W 69.9' "N1/16 8T"
 Set nails/tags in the 1965 wits:
 14" Soft Maple S42E 49.1'
 20" Soft Maple N13W 46.6'
 Bearings magnetic

Signed by Stephan J. Szyszkoski Date 1-27-94
 Surveyor's Michigan License No. 33986