

✓

**MICHIGAN**  
**DEPARTMENT OF CONSERVATION**  
**FORESTRY DIVISION**

**LAND CORNER RECORD**

T.42 N NR 10 W . . .

----- Mackinac -----

----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 4-5-8-9 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 15" W. Pine ----- S 26° E 97 links  
"S 9 NBT" -----

6" Cedar ----- N 10° E 42 links  
"S 4 NBT" -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established section corner by measurement to stream 120 links east, 50 links south and 78 links west.

Found possible tamarack stump bottom bearing S 73° W 12 links.

Found 24" white pine about 2 chs. east with old blazes on east & west sides. Blazes 60 years old (by annual ring count).

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 7/17/57  
REGISTERED LAND SURVEYOR