

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T42... NR 10 = 11 W

Mackinac COUNTY

DESCRIPTION OF CORNER section corner for sections 6 - 7 - 1 - 12

DESCRIPTION OF CORNER MONUMENT 1½" iron pipe

WITNESSES TO CORNER 1-21-58

8" cedar N 32°, E 22 links. Marked "S6NBT"

9" cedar S 15°, E 24½ links. Marked "S7NBT"

8" tamarack N 36° W 35 links. Marked "S1NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Re-witnessed corner. Found iron pipe in place. Found 3 original tamarack bearing trees, bearing S 49°, W 25 links; N 61°, E 48 links and S 45°, E 40 links. (green). All bearing trees in good condition. Corner lies in N - S fence line and in swamp. Corner found by Forestry Division Survey Crew.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 6-18-59  
REGISTERED LAND SURVEYOR