

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 42. NR. 10 West

Mackinac COUNTY

DESCRIPTION OF CORNER section corner for sections 5 - 6 - 7 - 8

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 2-24-58

16" white pine N 82°, W 229 links. Marked "561BT"

8" white pine S 49°, W 247 links. Marked "871BT"

3" white pine, east 81 links, marked "K".

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Re-established corner by double proportionate measure, from corners:  
1/4 corner 1/2 mile north, 1/4 corner 1/2 mile east, section corner 1 mile south,  
section corner 1 mile west. Found no evidence of original corner.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler DATE 6-12-59  
REGISTERED LAND SURVEYOR