

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Mackinac  
 \_\_\_\_\_  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |   |            |   |            |           |
|------------------------------------|---|------------|---|------------|-----------|
| 1. Public Land Survey              | T | <u>42N</u> | R | <u>10W</u> | <u>E1</u> |
|                                    | T | _____      | R | _____      | _____     |
|                                    | T | _____      | R | _____      | _____     |
|                                    | T | _____      | R | _____      | _____     |
| 2. Property Controlling in Section | S | _____      | T | _____      | R         |
|                                    | S | _____      | T | _____      | R         |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____      | R         |
|                                    | S | _____      | T | _____      | R         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Oct 16 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(E1) Corner common to Sections 4-5 T42N-R10W and Sections 32-33 T43N-R10W. Reestablished and recorded in 1958 by Billy D. Buckler, RLS. 1" pipe with 4" brass cap. 14" Red Pine S13E 128 links, 15" Red Pine S41W 123 links, 16" Red Pine N01E 150 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E1) Recovered the 1958 monument as described, a 1" ID iron pipe capped with a 4" dia. brass State of Michigan tablet, appropriately stamped, in good condition, and at record bearing and distance from the 1958 witness trees, recovered in good condition with overgrown blazes. Left the monument in place, marked new BH blazes on the 1958 NBT's and made one new witness tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E1) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following:  
 16" R.Pine S10E 84.6' "S4 NBT"  
 18" R.Pine S42W 82.2' "S5 NBT"  
 18" R.Pine N03E 99.7' "S33 NBT"  
 6" R.Pine N60W 15.3' "S32 NBT"  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 4/18/00  
 Surveyor's Michigan License No. 33986