

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Mackinac COUNTY  
T 42N R 11W

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 29-30-31-32

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7-15-69

WITNESSES TO CORNER..... 9" Hard Maple (S30 NBT) N66°W 34.0'



8" W. Birch (S32 NBT) S11°E 15.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original witness; a cedar, bearing N50°W 33 Links, tree down and in poor condition. Found remains of both faces with numerous old blazes. Found old blazes to South and West, on old down timber. Distance checks to swamp edge South (2.00 chs) and to an original  $\frac{1}{4}$  Cor.,  $\frac{1}{2}$  mile East.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE

9-28-71

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68