

FOR CORNERS OF--

LOCATED IN--

CORNER CODE NUMBER

1. PUBLIC LAND SURVEY _____ T. 42 N. X, R. 11 E. X W. X C-12

2. PROPERTY CONTROLLING IN SECTION 31 T. 42 N. X, R. 11 E. X W. X 14, E-12

3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____, R. _____ S. _____, R. _____ E. _____ W. _____

4. LOT NO. _____, RECORDED PLAT _____

5. PRIVATE CLAIMS _____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-10, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-12 1/4 corner on East side of sec. 31. O.E.T.'S. 6" Beech, N32°W, 20 lks.
7" Beech, S58°E, 46 lks.

14 South 1/16 corner on East side of sec. 31. Not prev. est.

B-12 Center of section 31. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-12 Set M.P.O.L. between N.E. and S.E. section corners.

14 Set M.P.O.L. between East 1/4 corner and Southeast section corner.

B-12 Set at intersection of North - South and East - West 1/4 lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 D.N.R. Monument. New Bearings: 7" H. Maple, N13°W, 7.5' & 6" H. Maple, N44°E, 10.05'
8" H. Maple, S10°E, 20.7' & 7" H. Maple, S56°W, 21.4'.

14 D.N.R. Monument. Bearings: 24" W. Pine, N6°E, 35.6' & 9" Balsam, N71°E, 48.2' &
10" W. Birch, S17°W, 30.2' & 5" Cherry, N80°W, 30.3'.

B-12 D.N.R. Monument. Bearings: 7" Cedar, N54°E, 25.4' & 4" Cedar, N29°W, 25.1' &
8" Cedar, S78°W, 52.8'.

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 1-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____

DATE _____