

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
Mackinac Co. 2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. 8. R. 11 E. W.	E-11
2. PROPERTY CONTROLLING IN SECTION 31	T. 42 N. 8. R. 11 E. W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-10, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B-11 1/4 corner North side of section 31. Bearings: Sugar 10", S66°E, 30 lks. &  
Sugar 12", N18°W, 20 lks. Wood Post for cor

/ West 1/16 on North side section 31. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B-11 Set M.P.O.L. between N.W. and N.E. section corners.

/ Set M.P.O.L. between N.W. section corner and North 1/4 corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 D.N.R. Monument. New Bearings: 12" R. Maple, S73°W, 24.5' & 8" R. Maple, N54°W, 28.8'  
8" Balsam, N10°W, 42.8' & 6" H. Maple, N45°E, 16.6'

/ D.N.R. Monument. Bearings: 9" Cedar, N4°E, 15.0' & 4" Cedar, S20°E, 12.2' &  
10" Cedar, S45°W, 23.8' & 12" Cedar, S62°E, 16.5'.

SIGNED BY

*David E. Babbitt*  
David E. Babbitt

DATE 1-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: