

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#14

For corners in
Mackinac
(County)

Located In:	Corner Code ##
1. Public Land Survey	T <u>42N</u> R <u>11W</u> <u>B12</u>
	T _____ R _____
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S <u>31</u> T <u>42N</u> R <u>11W</u> <u>14</u>
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on June 06, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	•	•	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

(B12) Center of Section 31. Corner established in 1983 by David B. Babbitt, RLS at the intersection of 1/4 lines. D.N.R. Monument, 7" Cedar N54E 25.4', 4" Cedar N29W 25.1', 8" Cedar S78W 52.8'. Found no subsequent record.
 (14-Sec. 31) South 1/16 corner between Sections 31-32. Corner established in 1983 by David B. Babbitt, RLS at M.P.O.L. between Quarter corner north and Section corner south. D.N.R. monument 24" W. Pine N6E 35.6', 9" Balsam N71E 48.2', 10" W. Birch S17W 30.2', 5" Cherry N80W 30.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B12) Found and accepted Babbitt's monument, as described, in good condition, and at record bearing and distance from his three BTs, all in good condition. Re-marked the top blaze and placed measuring nails in all three and marked one new witness as described below.
 (14-Sec. 31) Found and accepted Babbitt's monument, as described, in good condition, and at record bearing and distance from his three remaining witnesses. The W. Pine is now a cut stump with bottom blaze visible, the W. Birch and Cherry are in good condition, the Balsam has been cut. Marked new top blaze in the Birch and Cherry, placed measuring nails in them, and marked two new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(312) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 10" Cedar N54E 25.8' "CS" 6" Cedar N29W 25.3' "CS" 10" Cedar S78W 53.1' "CS" 4" Maple S52E 26.9' "CS BT" An older 4" squared and scribed cedar post is adjacent. Bearings are magnetic.	(14-Sec. 31) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and placed measuring nails in the following: 12" W. Birch S17W 30.3' "S1/16" 8" Cherry N80W 30.7' "S1/16" 4" W. Birch S76E 26.6' "S1/16" 6" Cherry N07W 20.2' "S1/16" Placed a 3" Cedar post adjacent. Bearings are magnetic.
---	--



Signed by Stephan J. Szyszkoski Date 9-7-95
 Surveyor's Michigan License No. 33986