

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	42N	R	11W	C12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	31	T	42N R 11W	15
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on June 06, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C12) Quarter corner common to Sections 31-32. Corner reestablished in 1983 by David B. Babbitt, RLS at M.P.O.L. between Section corners North and South. D.M.R. monument, 7" H. Maple N13W 7.5', 6" H. Maple N44E 10.05', 8" H. Maple S10E 20.7', 7" H. Maple S56W 21.4'. Found no subsequent record.

(15-Sec. 31) West 1/16 corner between Section 31 T42N-R11W and Section 6 T41N-R11W. Corner established in 1969 by Billy D. Buckler in line with fence to north and 29.0' South of fence corner. Buried 1.25"x30" iron pipe in road, at corner. 18" H. Maple W67E 72.8'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C12) Found and accepted Babbitt's monument as described, in good condition, and at record bearing and distance from his 1983 witnesses, all in good condition. Marked new top blazes on all of these witnesses and set measuring nails in them.

(15-Sec. 31) Found and accepted Buckler's buried monument, as described, in good condition, and at record bearing and distance from his 1969 accessory, in good condition. Left the monument in place and took three new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C12) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:
 9" H. Maple N13W 7.8' "1/4S"
 8" H. Maple N44E 10.3' "1/4S"
 10" H. Maple S10E 21.0' "1/4S"
 9" H. Maple S56W 21.9' "1/4S"
 Placed a 3" squared and scribed cedar post adjacent.

(15-Sec. 31) Found 1.25" iron pipe buried in road. Set nails and tags in trees:
 4" Cherry N72W 43.0'
 8" Apple N75W 92.0'
 Newton Twp sign 17102 N75E 33.1'
 Location poster on squared post 33' north. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 9-7-1995

Surveyor's Michigan License No. 33986