

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

17

For corners in
Mackinac

	(County)	Located In:	Corner Code #
1. Public Land Survey		T <u>42N</u> R <u>11W</u>	<u>A13</u>
		T <u>42N</u> R <u>11W</u>	<u>B13</u>
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on November 29, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A13) Corner common to Townships 41-42N and Ranges 11-12W. Corner replaced in 1960 by Billy D. Buckler, RLS at the location of an old wood post. D.N.R. monument, 15" W. Pine N50E 38.5 links, 4" Cedar S15E 84 links, 5" Cedar N30W 60 links.
 (B13) Quarter corner common to Section 31 T42N-R11W and Section 6 T41W-R11W. Corner replaced in 1969 by Billy D. Buckler, RLS in center of E-W road and between two fence corners. Buried 1"x36" iron pipe, 6" Cedar S40E 37.5', 8" Cedar S22W 53.7'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A13) Found Buckler's DNR monument buried just north of the north edge of road, in good condition, and at record bearing and distance from this W. Pine and Cedar NW NBTs. Re-Marked top blaze on these two witnesses, placed measuring nails in them, and marked two new bearing trees as described below. The Cedar SE NBT has been cut.
 (B13) Found Buckler's monument, as described, in good condition, and at record bearing and distance from his SE cedar NBT. The other NBT has been cut. Also recovered 3 additional NBTs marked with blazes and scribing in 1983. Re-marked top blazes and placed measuring nails in all remaining trees as described below. The corner monument falls in the center of E-W road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A13) Found 1" pipe with DNR cap, buried. Blazed, scribed and placed measuring nails in the following: 20" W. Pine N50E 26.0' 8" Cedar N30W 39.5' 5" Cedar West 62.5' 4" Spruce S15E 34.25' Bearings to the new NBTs are magnetic.	(B13) Found 1" buried iron pipe. Blazed, scribed, and placed measuring nails in the following: 10" Cedar S42E 37.8' "1/4S" 8" Cedar N05E 35.15' "1/4S" 6" Cedar N56E 34.8' "1/4S" 14" Cedar N80E 78.9' "1/4S" Bearings are magnetic.
---	---



Signed by Stephan J. Szyszkoski Date 9-7-1995
 Surveyor's Michigan License No. 33986