

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

15

For corners in
Mackinac

County	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>31</u> T <u>42N</u> R <u>11W</u>	<u>5</u>
	S <u>31</u> T <u>42N</u> R <u>11W</u>	<u>12</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on June 06, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 31) North 1/16 corner, Section 31. Corner not established in the original survey. Found no subsequent record.
 (12-Sec. 31) South 1/16 corner, Section 31. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 31) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between monumented Quarter corner 1333.31' North and monumented Center of Section 1333.31' South. At the position for the corner, I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (12-Sec. 31) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between monumented Center of Section 1330.52' North and monumented Quarter corner 1330.52' South. At the position for the corner I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner, an old downed wire fence is about 9' easterly.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5-Sec. 31) Set 1" pipe with 4" MOHR cap. Blazed, scribed, and set measuring nails in the following:	(12-Sec. 31) Set 1" pipe with 4" MOHR cap. Blazed, scribed, and set measuring nails in the following:
14" W. Birch N49E 17.0' "N1/16 BT"	14" Cedar N68E 3.85' "S1/16 BT"
14" W. Birch S08E 17.65' "N1/16 BT"	16" Beech S31E 29.3' "S1/16 BT"
8" Maple S42W 18.9' "N1/16 BT"	6" Maple S44W 20.3' "S1/16 BT"
8" Maple S77W 31.35' "N1/16 BT"	8" Cedar S56W 5.1' "S1/16 BT"
Placed a 5" squared and scribed cedar post adjacent and a location poster on an 8" maple 45.5' south. Bearings are magnetic.	Placed an old cedar fence post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 9-7-95
 Surveyor's Michigan License No. 33986