

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac

(County)

Located in:

Corner Code #

- |                                    |   |             |
|------------------------------------|---|-------------|
| 1. Public Land Survey              | T <u>42N</u> R <u>11W</u>                 | <u>M1</u>   |
|                                    | T <u>42N</u> R <u>11W</u>                 | <u>M2</u>   |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Sep 29 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:


- (M1) Corner of townships T42-43N, R10-11W. 1958 - Remonumented by Billy D. Buckler RLS at the position of a 1.5" dia. iron pipe which he found at a fence corner and at record bearing and distance from the remains of the Tamarack OBT N14W 6 links. Set 1" pipe with 4" brass cap. 6" Aspen S50W 17 links, 6" Aspen N44E 28 links, 7" W.Birch N24W 53 links.  
 (M2) Quarter corner common to Section 6 T42N-R11W and Section 1 T42N-R10W. 1958 - Billy D. Buckler found and accepted a 1.25" dia. iron pipe in a N-S fence at record bearing and distance from remains of probable Cedar OBT N44W 14 links. Mr. Buckler's witnesses: 7" Cedar S33W 44 links, 9" Cedar S86W 56 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (M1) Recovered the 1958 monument in good condition, with the 1.5" dia. iron pipe noted in the 1958 record, adjacent. The remains of the OBT Tamarack were not recovered. The remains of the 1958 NBTs were not recovered. The monument is at a fence corner with old fencing running south and west. Left the monument in place and made new witnesses as described below.  
 (M2) The 1.25" iron pipe noted in the 1958 record was not recovered. Remonumented the corner in the remains of the N-S fence noted in the 1958 record and at record bearing and distance from the two 1958 Cedar NBTs, both found in good condition with overgrown blazes. The probable original BT cedar, noted in Mr. Buckler's record, was not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (M1) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with tag in:<br>10" W.Birch S25E 32.35' mrkd "S6 NBT"<br>10" W.Birch S61E 25.45' do<br>8" Balsam South 33.85' mrkd "S1 NBT"<br>5" Balsam N47E 33.4' mrkd "S31 NBT"<br>Bearings are magnetic. Distances are to nail with tag. | (M2) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with tags in:<br>12" Cedar S32W 29.25' mrkd "1/4S" *<br>18" Cedar N89W 37.3' mrkd "1/4S" *<br>6" W.Birch S21E 13.2' mrkd "1/4S NBT"<br>6" W.Birch N45E 14.85' do<br>Bearings are magnetic. Distances are to nail with tag. * denotes 1958 NBT. |
|---|--|



*Stephan J. Szyszkoski*

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/7/04