

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_

2. Property Controlling  
 in Section

S 21 T 42N R 11W 14  
 S 21 T 42N R 11W 15

3. Miscellaneous  
 Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Nov 30 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:


- (14-Sec. 21) South 1/16 corner between Sections 21 and 22. Not established in the original survey.
- (15-Sec. 21) West 1/16 corner between Sections 21-28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (14-Sec. 21) Established the corner midway and on line between Section corner 1337.56' south and Quarter corner 1337.56' north.
- (15-Sec. 21) Established the corner midway and on the section line between Section corner 1335.84' West and Quarter corner 1335.84' East. From the corner thus established, the center of an E-W trail road is 7 feet south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| (14) Set a chisled "+" on a boulder 6" below ground surface in easterly rut of a N-S trail. Set measuring nails in:<br>5" Spruce N28E 16.0' mrkd "S1/16 BT"<br>4" Spruce N10W 41.75' do<br>4" Spruce N28W 41.75' do<br>4" Spruce S36W 44.3' do<br>Bearings are magnetic. Distances are to nail with tag. | (15) Set 5/8"x24" rebar w/plastic cap "MICH DNR PS33986" made firm in a mound of stone. Set measuring nails in:<br>10" Spruce S04E 25.0' mrkd "W1/16 BT"<br>6" Balsam S57W 30.05' do<br>10" Maple N60W 11.65' do<br>8" Maple N07E 6.3' do<br>Placed cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|---|



*Stephan J. Szyszkoski*

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/7/04