

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41-42NR. 12W. . .

----- Mackinac ----- COUNTY

DESCRIPTION OF CORNER ----- Sec. Cor. 5-6-31-32 -----

DESCRIPTION OF CORNER MONUMENT ----- 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER ----- 10" H. Maple (S32 NBT) N56°E 42 Lks. -----

----- 9" H. Maple (S 5 NBT) S60°E 35 Lks. -----

----- 15" W. Pine (S6 NBT) S72°W 114 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Cor. from two W. Birch stps., both recently cut, bearing S35°W 18 Lks. and S23°E 28 Lks. Found overgrowth of both faces and determined age by actual ring count. Bor. lies 40 Lks. north of escarpment. Cor. placed and wit. 6/4/59 with B. McDonald, Aide.

SURVEYORS SEAL

Billy D. Buckler
SIGNED ----- Billy D. Buckler ----- DATE 7/29/59 -----
REGISTERED LAND SURVEYOR