

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 42 NR 12W

----- Mackinac ----- COUNTY

DESCRIPTION OF CORNER ----- Sec Cor. for Secs: 13-14-23-24 -----

DESCRIPTION OF CORNER MONUMENT ----- 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER ----- 8" Cedar (S13 NBT) N4^oE 62 Lks. -----

----- 9" Cedar (S24 NBT) S68^oE 31 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced from Tam. B.T. bearing S 27^oW 19 Lks. Found calloused overgrowth and several scribe marks on lower face. Found 6" Tam. stub S14^oW 20 $\frac{1}{2}$ Lks. scribed "S23". Appears to be an extra witness. Many old blazes at cor. Cor. lies in north edge of spruce swp. and 25 Lks. east of old logging road. Cor. placed and wit. 5/8/59 with J. Halbach, D.F.

SURVEYORS SEAL

SIGNED Billy D. Buckler
Billy D. Buckler DATE 7/29/59
REGISTERED LAND SURVEYOR