

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 42. NR. 12. W

Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28, 29, 32, and 33

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 6" Hard Maple (S 32 NBT) S 32° W 30 Links

6" Hard Maple (S 33 NBT) S 70° E 56 1/2 Links

6" Hard Maple (S 29 NBT) N 72° W 10 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED. This corner was set by double proportionate measurements. No original  
evidence.

Corner was placed and witnessed September 17, 1959.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/29/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler