

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 41-42 NR 12 W

Mackinac COUNTY

DESCRIPTION OF CORNER Section corner for Sections 32 and 33 T 42 N, R 12 W
and Sections 4 and 5, T 41 N, R 12 W

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 5" Cedar (S 5 NBT) S 08° W 45 Links

8" Cedar (S 33 NBT) N 89° E 32 Links

5" Cedar (S 32 NBT) N 48° W 09 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was set on E and W blazed line and on west edge at N - S
Road which is believed to be built on Section line. Distances to streams to
north and south and west agree with Government Field Notes. Corner agree with
positions of other corners in area. Squared and scribed 5" Cedar for corner.

Corner was placed and witnessed September 17, 1959.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 2/29/60