

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION



LAND CORNER RECORD

T.42.. NR..12..W

..Mackinac..COUNTY

DESCRIPTION OF CORNER Meander Corner for Sections 26 and 27 on North side  
of Batty Doe Lake.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 9" Cedar (M.C. NBT) N 56° W 62 Links

12" Cedar (M.C. NBT) N 52° E 42 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED. This corner was replaced from two original Cedar B.T.'s a stub  
bearing N 34° W 07 Links and stump bearing N 57° E 20 Links. Found an  
unrecorded witness tree bearing N 13° E 08 Links. Found scribe marks on  
this tree.

Corner was placed and witnessed March 2, 1960 with Region I Survey Crew.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 4/29/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler