

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. T42N N.R. 12W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/2 Cor. Between Secs. 16 & 21.

CORNER MONUMENT 1" pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 8-11-69

WITNESSES TO CORNER..... 12" Cedar (1/2 S NBT) S18°E 14.7'



9" Cedar (1/2 S NBT) N28°E 17.9'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from one possible witness, a 24" Cedar, down and in poor condition. Found old scars and possible blazes in proper position. Found a Cedar stump with a blazed face to south of corner. This falls on an old cutting edge.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 12-30-69
REGISTERED LAND SURVEYOR