

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N.R. 12 W


Mackinac COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Sec. 16-17-20-21.

CORNER MONUMENT 1" pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8-11-69

WITNESSES TO CORNER..... 10" Cedar (S17 NBT) N3⁰W 7.8'



9" Cedar (S16 NBT) N68⁰E 9.3'

9" Cedar (S20 NBT) S66⁰W 14.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one probable witness; a down Cedar bearing $N77^{\circ}E$, 24 links. This tree has a badly rotted face with no positive identification. Position checks very well with other corners in the area. Found a very old blazed line running N-S, about 12° East of the Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 12-30-69