

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 42 N.R. 12 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to sections 17-1819-20.

CORNER MONUMENT 5/8"x16" Iron Bar buried in the center of the North-South road.

DATE MONUMENT PLACED AND WITNESSED 10-27-69

WITNESSES TO CORNER..... 9" Balsam (S17 NBT) N48°E 19.4°



8" Aspen (S18 NBT) N67°W 35.2°

8" Aspen (S19 NBT) S48°W 39.2°

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by proportionate measure between corners; one mile North and one mile South. Corner lies in a straight line between the section corners and in the N-S road. The distance East to a stream and to the Section Corner one mile east checks well.

Found some blazes along this line to the West, all were less than ten years old.

SURVEYOR'S SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 12-30 -69  
REGISTERED LAND SURVEYOR