

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42-43 N.R. 12 W


Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 1-2-35-36

CORNER MONUMENT 1 inch iron pipe with 4 inch Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 11-10-69

WITNESSES TO CORNER..... 10 inch Cedar (S36 NBT) N83°E 16.5°



11 inch Cedar (S2 NBT) S41°W 49.0°

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner lies 100' South of a woods road and 30' East of an older Skidding road.

This Corner replaced at an old Wood Post found By E. A Sainio, R.L.S. about 1959. This location fits location of old Railroad Survey dating before 1900.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 12-30-69
REGISTERED LAND SURVEYOR