

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Mackinac Co. One Corner

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|-----------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 42 N. 8 th R. 12 W. | G-3 |
| 2. PROPERTY CONTROLLING IN SECTION- | T. - N. S. R. - E. W. - | |
| 3. MISCELLANEOUS PROPERTY IN SECTION- | T. - N. S. R. - E. W. - | |
| 4. LOT NO. , RECORDED PLAT. | | |
| 5. PRIVATE CLAIMS. | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9-4 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-3 Sec. Cor. 3-4-9-10, set by Guy C. Carleton, D.S. 1849.
 Bearings were: Fir 6", N70°W, 6 lks. and Spruce 6", S68°W, 17 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-3 Found an old wood post with line of blazes, South to railroad. blazes are more than 40 years old. Position checks very well with railroad as indicated on a Survey map dated 1889.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3 Placed 1" pipe with 4" aluminium cap at corner.
 New bearings: 12" Cedar, N13°E, 8.1' and 8" Cedar, S59°W, 13.4'

SIGNED BY: Billy D. Buckler

DATE: 2-22-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ CHIEF OF SURVEY PARTY

DATE: _____

APPROVED AND SIGNED BY: _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE: _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____