

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>42N</u> R <u>12N</u>	<u>86</u>
	T <u>42N</u> R <u>12W</u>	<u>85</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

85 Jul 01 2004
 86 Jun 30 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5		●											
6		●		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (86) Center of Section 18. Not established in the original survey.
 (85) Quarter corner common to Sections 7-18. 1849: Established by Guy Carleton: "East corrected between sections 7 & 18...41.47 Set post for 1/4 section corner. Cedar 6 N86E 17 links, Cedar 14 S57W 15 links. ... 81.47 Section corner."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (86) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
 (85) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record and on the section line between Section corners 2690.10' West and 2594.75' East. The position for the corner falls 1' west of the center of a N-S road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(86) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 4" Balsam S09E 25.3' "CS BT" 4" Balsam S75E 6.0' do 4" Balsam N61E 7.4' do 4" Balsam N18E 7.7' do Bearings are magnetic. Distances are to nail with tag. Bend in road (N&E) is approx. N45W 90' distant.	(85) Set 5/8"x30" rebar with plastic cap stamped "MICH DMR PS 33986". C/L RR Xing sign post N40E 29.25' RR Xing sign post N12W 47.3' nail/tag Stop sign post N36W 102.55' do C/L of railroad N04W 35.2' Bearings are magnetic.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/7/04