

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac
 (County)

Located In:	Corner Code #
1. Public Land Survey	T ___ R ___
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S <u>18</u> T <u>42N</u> R <u>12W</u> <u>11</u>
	S <u>18</u> T <u>42N</u> R <u>12W</u> <u>8</u>
3. Miscellaneous	S ___ T ___ R ___
Property in Sec.	S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 30 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		● 10		17		16		15		14		13	
7		●											
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (11-Sec. 18) Southwest 1/16 corner, Section 18. Not established in the original survey.
 (8-Sec. 18) West 1/16 corner, Section 18. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (11-Sec. 18) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (8-Sec. 18) Established the corner at 20 chains, proportionate to the original record, west of the Center of Section 18 and on a straight line between the Center and the W1/4 corner. Measured distances to the Center and 1/4 corner are 1312.66' and 1397.00', respectively.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 6" W.Birch N06W 19.0' SW1/16 BT
 5" Spruce N12W 35.8' do
 4" W.Birch S20E 9.0' do
 12" W.Birch N47E 54.2' do
 Bearings are magnetic. Distances are to nail with tag.
 (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 5" Balsam N77W 8.1' W1/16 BT
 12" Spruce N08W 18.1' do
 5" Maple N47E 11.55' do
 10" Balsam S37W 29.45' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 7/7/04
 Surveyor's Michigan License No. 33986