

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>42N</u> R <u>12W</u>	<u>B13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>31</u> T <u>42N</u> R <u>12W</u>	<u>15</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 25 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

(B13) Quarter corner common to Section 31 T42N-R12W and Section 6 T41N-R12W. 1845 - Established by John Burt, US Deputy Surveyor: West on South side of Section 31 ...40.00 Set qr. section post. W.Birch 4 N27E 36 links, W.Birch 4 N51W 100 links. ... 81.81 intersected Range line 3.90 south of post and set post corner of T41 & 42 between R12 & 13W. Found no subsequent record.
 (15-Sec. 31) West 1/16 corner between Section 31 T42N-R12W and Section 6 T41N-R12W. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B13) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record between Township corner 2769.06' West (recorded in Liber 4 Page 655 Schoolcraft Co. records) and Standard Section corner 2649.19' East (a perpetuated original corner).
 (15-Sec. 31) Established the corner 20 chains, proportionate to the original record, west of Quarter corner 813 and on the Township line between Township corner 1444.47' West and Quarter corner 1324.59' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 11" R.Pine S64E 26.85' mrkd "1/4S NBT" 15" R.Pine N55E 48.75' do 14" W.Pine N01W 37.8' do 10" Cedar S18W 66.35' do Bearings are magnetic. Distances are to nail with tag.	(15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Spruce S58E 31.45' mrkd "W1/16 BT" 7" Cedar S22W 6.1' do 5" Cedar S52W 14.35' do 10" Cedar S68W 12.9' do Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/9/06