

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac

(County)

Located In:

Corner Code #

- |                                    |                                           |             |
|------------------------------------|-------------------------------------------|-------------|
| 1. Public Land Survey              | T <u>42N</u> R <u>12W</u>                 | <u>C13</u>  |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous                   | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| Property in Sec.                   | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Feb 09 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C13) Corner common to Sections 31-32 T42N-R12W and Sections 5-6 T41N-R12W. 1959 - Remonumented by Billy D. Buckler RLS from two W.Birch stumps, believed to be the remains of the original BTs. Set 1" pipe with 4" brass cap. 10" Hard Maple N56E 42 links, 9" H.Maple S60E 35 links, 15" W.Pine S72W 114 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C13) The 1959 monument was not recovered. Remonumented the corner at record bearing and distance from the remaining two 1959 NBTs, the Hard Maples SE and SW, both in good condition. The Hard Maple NE was not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:  
 13" Sugar S61E 23.15' mrkd "S5" \*  
 9" Cedar S42E 32.9' "S5 NBT"  
 18" Y.Birch N39W 28.7' "S31 NBT"  
 26" W.Pine S73W 77.3' "S6"  
 Bearings are magnetic. Distances are to nail with tag. \* denotes 1959 NBT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/9/06