

SURVEY & REMONUMENTATION

MAR 13 1998

MACKINAC COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>3W</u>	M-5
	T <u> </u> R <u> </u>	Sec. Cor. common to Sec's 12 & 13
	T <u>42N</u> R <u>2W</u>	A-5
	T <u> </u> R <u> </u>	Sec Cor common to Sec's 7 & 18
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	

RECEIVED & FILED
DIVISION OF MICHIGAN
REGISTERED LAND SURVEYORS
DEC 29 1997
AM PM
7/8/91 1/2/3/4/5/6

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Neil E Hill, in a field survey on DEC 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1840 GLO notes William Burt 10" Cedar S26W 22 lks
11" Tamarack N42W 16 lks

1980 James Granger found 4"x4" concrete monument with tag dated 11-76
Recorded Liber B, page 190
Recorded by U.S.F.S Plat of Survey No. 4, T42N, R2W, A-5.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


1997 Found 4"x4" concrete monument. Accepted corner position. (Old witnesses)
8" Cedar N73E 31.08 feet
6" Cedar S14E 37.37 feet
8" Cedar S22W 20.95 feet
6" Cedar S81W 41.84 feet

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 11-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4"x4" concrete monument

	(Face)	(Side nail)
7" Cedar N78E	31.1'	31.22'
7" Cedar S13E	37.3'	37.27'
7" Cedar S27W	21.5'	21.17'
7" Cedar S81W	41.9'	41.60'
Sign Post West	5.0'	



Signed by Neil E. Hill P.S.
Surveyor's Michigan License No. 27447

Date DECEMBER 22, 1997