

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION MACKINAC COUNTY REMONUMENTATION CORNER

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac Located In: Corner Code #
(County)

1. Public Land Survey T 42N R 3W M-6
E 1/4 Cor. Sec. 13
T 42N R 2W A-6
W 1/4 Cor. Sec 18
T ___ R ___
T ___ R ___
2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

RECEIVED & FILED
DIVISION OF RECORDS
MACKINAC COUNTY REGISTER OF DEEDS
DEC 29 1997
AM PM
718 514 1143 11510

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Neil E Hill, in a field survey on DEC 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1840 GLO notes William Burt 6" Aspen S66W 6 lks
5" Aspen N57W 40 lks

1980 James Granger found iron by T.L. Jackson from survey dated 1969
Recorded Liber B, page 190

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Found 1/2" iron pipe. Accepted corner location.
14" Spruce S69E 41.41' (Old witnesses)
8" Aspen S01W 20.51'
12" Aspen N15W 22.22'

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 11-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed 1/2" pipe. Set 5/8" rod with remonumentation cap at location.
16" Poplar N80W 09.37'
8" Poplar S15W 20.75'
20" Spruce S65E 42.03
8" Poplar N10E 38.67' (F.F.S. Marker Tree)



Signed by Neil E Hill P.S.
Surveyor's Michigan License No. 27447

Date DECEMBER 22, 1997