

**SURVEY & REMONUMENTATION**

MAR 13 1998

**MACKINAC COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>3W</u> K-4	<u>1/4</u> Cor common to Sec's 11 & 12
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

RECEIVED & FILED  
DIANE FRANK KNOX  
MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997  
AM PM  
7:18:14

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11	●	12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Neil E. Hill, in a field survey on DEC 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840 GLO notes William Burt 6" Fir S41W 11 lks  
8" Aspen S81W 4 lks

No records of this corner being perpetuated, however various surveys indicate this corner's position


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 No evidence of corner.  
Set midway and on line between Section Corners North and South.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 11-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" rod with remonumentation cap.  
6" Spruce N45E 05.03'  
18" Twin poplar S65E 17.80'  
20" Dead poplar Due South 13.02'  
6" Poplar S80W 54.53'



Signed by Neil E. Hill P.S.  
Surveyor's Michigan License No. 27447

Date DECEMBER 22, 1997