

**SURVEY & REMONUMENTATION**

**MAR 13 1998 MACKINAC COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION  
For corners in

Mackinac Located In: Corner Code #  
(County)

1. Public Land Survey T 42N R 3W L 5  
T     R     1/4 Cor common  
T     R     to Sec's 12 & 13  
T     R      
T     R    

2. Property Controlling S     T     R      
in Section S     T     R    

3. Miscellaneous S     T     R      
Property in Sec. S     T     R    

RECEIVED & FILED  
DUNBAR & NEVICH  
REGISTERED PROFESSIONAL SURVEYORS OF DEEDS

DEC 29 1997

AM 11:51:11-11:51:12 12/31/97

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Neil E Hill, in a field survey on DEC 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840 GLO notes Wiliam Burt 10" Birch N5E 15 lks  
GLO notes distance 2629.44 East & West 8" Cedar S13W 8 lks 2628.789' C  
No records of this corner being perpetuated

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Found no evidence of corner.  
Set midway and on line at 2628.79' between Section Corners East & West.

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 11-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" rerod with remonumentation cap near two track road that turns from East and goes North.

5" W. Birch S10W 76.95'  
8" Spruce S45W 52.10'  
2" Spruce Due West 11.41'  
1/2" Iron N33E 21.82' (Believe set by Bishor)



Signed by Neil E Hill P.S.  
Surveyor's Michigan License No. 27447

Date DECEMBER 22, 1997

E-177