

**SURVEY & REMONUMENTATION**

MAR 13 1998

**SECTION MACKINAC COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>3W</u>	<u>M-4</u> ✓ E 1/4 Cor, Sec 12
	T ___ R ___	<u>A-4</u> W 1/4 Cor, Sec 7
2. Property Controlling in Section	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____

RECEIVED & FILED  
DWAYNE WALKER, CLERK  
MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997

AM PM  
7[8]9[0]1[1]2[2]3[3]4[4]5[5]6

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Neil E. Hill, in a field survey on DEC. 22, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO William Burt 1840 14" Tamarack S41W 66 lks  
10" Spruce N14W 18 lks

No records of this corner being perpetuated, however various surveys indicate this corner's position  
Recorded in T42N, R2W, U.S.F.S. survey No. 4.  
Found post of corner recovered by County Surveyor in 1940.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Found U.S.F.S. concrete post. Accepted location.

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 11-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
4"x4" concrete monument.

		(Face)	(Side Nail)
6" Cedar	N36W	7.6'	08.17'
6" Cedar (leaning)	S10E	10.2'	09.60'
9" Cedar	S38E	52.9'	52.97'
Sign Post	West	3.0'	
6" Cedar	S70W		07.74' (New)



Signed by Neil E. Hill P.S.  
Surveyor's Michigan License No. 27447

Date DECEMBER 22, 1997