

**SURVEY &  
REMONUMENTATION**

**MAR 13 1999 MACKINAC COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>3W</u>	<u>M-6</u> ✓ <u>E 1/4 Cor. Sec. 13</u>
	T <u>42N</u> R <u>2W</u>	<u>A-6</u> <u>W 1/4 Cor. Sec 18</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED & FILED  
DECEMBER 29 1997  
MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997  
AM \_\_\_\_\_ PM \_\_\_\_\_  
718] 21 19 97 14 3 4 5 16

Register of Deeds Stamp & File Number

I, Neil E. Hill, in a field survey on DEC 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1840 GLO notes William Burt 6" Aspen S66W 6 lks  
5" Aspen N57W 40 lks
- 1980 James Granger found iron by T.L. Jackson from survey dated 1969  
Recorded Liber B, page 190

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997 Found 1/2" iron pipe. Accepted corner location.  
14" Spruce S69E 41.41' (Old witnesses)  
8" Aspen S01W 20.51'  
12" Aspen N15W 22.22'

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 11-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Removed 1/2" pipe. Set 5/8" rered with remonumentation cap at location.
- 16" Poplar N80W 09.37'
- 8" Poplar S15W 20.75'
- 20" Spruce S65E 42.03'
- 8" Poplar N10E 38.67' (F.F.S. Marker Tree)



Signed by Neil E. Hill P.S.  
Surveyor's Michigan License No. 27447

Date DECEMBER 22, 1997