

1994 Mackinac County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners

Mackinac County

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>42N</u> R <u>4W</u> | <u>A-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

RECEIVED & FILED
 DIANE FRANKOVICH
 MACKINAC COUNTY REGISTER OF DEEDS

NOV 09 1994
 AM _____ PM _____
 7 8 9 10 11 12 1 2 3 4 5 6

Register of Deeds Stamp & File Number

I, David B. Guthrie, in a field survey on July 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: Established by Wm Burt, G.L.O. Survey
 Set a wood post and referenced:
 Tamarack 6/S36W/32
 Spruce 6/N65W/5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1" Square bolt 7' South of the Centerline of Green Road.
 (Source unknown)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Set Mackinac County Remonumentation Corner
 as 5/8" by 24" Iron Rod with a 3" aluminum cap stamped to identify,
 set 6" below the road gravel surface.

Referenced:
 S18°E - 28.14 feet - 8" Balsam
 S02°W - 19.43 feet - 12" White Birch
 N45°E - 37.83 feet - 15" Cedar
 N11°E - 41.25 feet - 8" Spruce

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE MACKINAC COUNTY
 SURVEY PEER GROUP AS THE
 OFFICIAL CORNER UNDER P.A.
 345 OF 1990 AT A MEETING
 HELD ON B-16-94

James A. Granger



Signed by David B. Guthrie

Date Oct. 21, 1994

Surveyor's Michigan License No. 22435